



LAKE HAVASU CITY

Community Investment Department

**NOTICE INVITING BIDS
SARA PARK TRAILHEAD IMPROVEMENTS RE-BID
PROJECT NO. PK1080RB
ADDENDUM NO. 1**

September 1, 2016

Attention is called to the following changes, additions, clarifications and/or deletions to the original solicitation and they shall be taken into account in preparing submissions:

There is no change in the opening date. **Submissions are due no later than 3:00 p.m., Arizona Time, SEPTEMBER 9, 2016**, at the City Clerk's Office, 2330 McCulloch Blvd. N., Lake Havasu City, AZ 86403.

ITEM	ACTION	DESCRIPTION or ISSUE
1:00	CHANGE	SARA Park Trailhead Public Restroom Building Plan Sheet A-4 note shall be changed: FROM: "2" STONE VENEER OVER MORTAR SETTING BED OVER 8X8X16 STANDARD CONCRETE MASONRY UNITS LAID IN RUNNING BOND PATTERN WITH REINFORCING PER STRUCTURAL DRAWINGS" TO: "2" STACKED NATURAL STONE VENEER OVER MORTAR SETTING BED OVER 8X8X16 STANDARD CONCRETE MASONRY UNITS LAID IN RUNNING BOND PATTERN WITH REINFORCING PER STRUCTURAL DRAWINGS"

3:00	ADD	<p>On Page 1210-8 of the Project Specifications add</p> <p>4.2.24a Septic Level Relay System</p> <p>The Contract Unit Price bid for this item shall constitute full compensation for furnishing all materials, labor, equipment, excavation and tools for the complete installation of the following:</p> <ul style="list-style-type: none"> • Float to indicate the vault at 85% capacity. • 1" Electrical Conduit and wire for float signal running parallel with the 4" PVC sewer from the vault to the restroom utility room. This includes a section of conduit that runs vertical through the slab of the building. The location shall be verified with the owner. • 1" spare Electrical Conduit stub from the utility room through the slab and extend approximately 5' beyond the footprint of the restroom. Final location to be verified with the owner. • 1" Electrical Conduit inside the building extending from the utility room through the roof. Location to be verified with the owner. • Solar panel capable of providing enough power for the relay system/float and 2 – 12V backup batteries. <p>Measurement and Payment for this item shall be per Lump Sum for the Septic Level Relay System complete in place.</p>
5:00	REPLACE	Section 00310 in its entirety with the attached:

September 1, 2016

Kimberly Fiumara, Procurement Specialist

****END OF ADDENDUM NO. 1****

SECTION 00310

BID SCHEDULE
LAKE HAVASU CITY

SARA Park Trailhead Improvements
PK1080RB

Lake Havasu City Council
Lake Havasu City
2330 N. McCulloch Boulevard
Lake Havasu City, AZ 86403

The City Council:

Pursuant to request for bids to be opened the 9th day of September, 2016 at 3:00 P.M., Arizona Time, at Room 109 of Lake Havasu City Hall, for the above project, the Contractor proposes to complete work, including furnishing all labor and materials, per the Specifications and Plans at the Following prices.

This Schedule of Items and Prices shall be completed in ink or typed by the Bidding Contractor. In case of discrepancy between the word and figure amount description, the word description shall control extensions.

Prices must be entered for each item and the appropriate subtotal and total blank shall be filled out. Bid prices shall include sales tax and all other applicable taxes and fees.

Bidder agrees to perform all the necessary work to complete the **SARA Park Trailhead Improvements, Project No. PK1080RB.**

SECTION 00310

<u>ITEM NO.</u>	<u>DESCRIPTION</u>	<u>ESTIMATED QUANTITY</u>	<u>UNIT OF MEASURE</u>	<u>UNIT PRICE ¹ (Word & Figure Amount)</u>	<u>ITEM TOTAL COSTS ²</u>
BASE BID					
1200.1	Mobilization, Bond, Insurance	1	L.S.	\$ _____	\$ _____
1200.2	Environmental Control Measures	1	L.S.	\$ _____	\$ _____
1200.3	Construction Staking	1	L.S.	\$ _____	\$ _____
1200.4	Grading, Excavation and Embankment	1,685	C.Y.	\$ _____	\$ _____
1200.5	Removal of Existing AC Pavement	446	S.Y.	\$ _____	\$ _____
1200.6	Removal of Existing Entry Monuments	3	EA	\$ _____	\$ _____
1200.7	Pavement Replacement, Transverse (MAG DET 200, Type B)	20	S.Y.	\$ _____	\$ _____
1200.8	2" Asphalt Concrete Pavement	1,868	S.Y.	\$ _____	\$ _____
1200.9	Aggregate Base Course, 4"	1,868	S.Y.	\$ _____	\$ _____

¹ The "Unit Price" column shall indicate unit or lump sum prices for each bid item and shall be indicated in written and numerical form.

² The "Item Total Costs" column shall indicate the extension of the unit prices, which is obtained by multiplying the "Estimated Quantity" column by the "Unit Price" column.

SECTION 00310

1200.10	Thickened Edge of Pavement (MAG. DET. 201, Type B)	100	L.F.	\$_____	\$_____
1200.11	Subgrade Preparation, 8"	1,868	S.Y.	\$_____	\$_____
1200.12	Concrete Curb and Gutter (MAG DET. 220, TYPE A)	222	L.F.	\$_____	\$_____
1200.13	Concrete Single Curb (MAG DET. 222, Type A)	408	L.F.	\$_____	\$_____
1200.14	Curb Opening	1	EA	\$_____	\$_____
1200.15	Curb Termination (MAG DET 222)	2	EA	\$_____	\$_____
1200.16	Concrete Bumper Block	4	EA	\$_____	\$_____
1200.17	Concrete Sidewalk (MAG DET. 230)	1,537	S.F.	\$_____	\$_____
1200.18	Sidewalk Ramp	2	EA	\$_____	\$_____
1200.19	Pavement Signing & Marking	1	L.S.	\$_____	\$_____
1200.20	Entry Gate	1	EA	\$_____	\$_____
1200.21	Install Decorative Boulders	6	EA	\$_____	\$_____
1200.22	Restroom installation	1	L.S.	\$_____	\$_____
1200.23	Relocate Shade Structure	1	L.S.	\$_____	\$_____

SECTION 00310

1200.24	Septic Tank, Vault, Excavation, and Installation	1	L.S.	\$ _____	\$ _____
1200.24a	Septic Level Relay System	1	L.S.	\$ _____	\$ _____
1200.25	Cutoff Wall	224	L.F.	\$ _____	\$ _____
1200.26	2" Water Service	321	L.F.	\$ _____	\$ _____
1200.27	4" PVC Sewer	120	L.F.	\$ _____	\$ _____
1200.28	4" PVC Sleeve	80	L.F.	\$ _____	\$ _____

BASE BID TOTAL³ \$ _____

Force Account 1 L.S. \$30,000.00 \$ _____

BID TOTAL + FORCE ACCOUNT \$ _____

³ The "Bid Total" amount shall be the sum of all costs listed in the "Item Totals Costs" Column

The unit prices for **SARA Park Trailhead Improvements, Project No. PK1080RB**, shall include all labor, materials, water disposal, bailing, shoring, removal, disposal, overhead, profit, insurance, and all other related costs and work to cover the finished work of the several kinds called for. Changes in the Contract shall be processed in accordance with Paragraph 16 of the General Conditions.

Bidder understands that the Owner reserves the right to reject any or all Bids, or portions thereof, and to waive any informalities in the bidding.

The Bidder agrees that this Bid shall be good and may not be withdrawn for a period of ninety (90) calendar days after the scheduled closing time for receiving Bids.

Upon receipt of written notice of the acceptance of this Bid, Bidder shall execute the formal Contract attached within 10 days and deliver a Performance Bond, Payment Bond, and Certificates of Insurance as required by Paragraph 25 of the General Conditions and the Special Provisions.

The Bid security attached in the sum of \$ _____ is to become the property of the Owner in the event the Contract and Bond(s) are not executed and provided within the time above set forth, as liquidated damages for the delay and additional expense to the Owner caused thereby.

Bidder hereby acknowledges receipt of the following Addenda: ____, ____, ____.

RESPECTFULLY SUBMITTED BY:

BY: _____

TITLE: _____

FIRM: _____

ADDRESS: _____

PHONE: _____ FAX _____

Seal - if Bid by a corporation

AZ Contractor's License No: _____ Type _____

** END OF SECTION **